

Generic Requirements for CCS Nodes Supporting M2PA IP-Based Virtual High-Speed Signaling Links (IPVHSLs)

Contents

Preface	Preface-1
1. Introduction	1-1
1.1 Purpose and Scope	1-1
1.2 Related Documents	1-2
1.3 Organization of This Document	1-2
1.4 Requirements Terminology	1-3
1.5 Requirement Labeling Conventions	1-4
1.5.1 Numbering of Requirement and Related Objects	1-4
1.5.2 Requirement, Conditional Requirement, and Objective Object Identification	1-5
1.6 Change Summary	1-5
1.6.1 Reasons for Reissue	1-5
1.6.2 Highlights of Principal Revisions and Additions	1-5
1.6.3 Change Markings	1-6
1.6.4 Detailed List of Substantive Revisions	1-6
2. Network and Protocol Architectures	2-1
2.1 Network Architecture	2-1
2.2 SS7 and Transport Protocol Architecture	2-2
2.2.1 Overview	2-2
2.2.2 Physical Layer	2-4
2.2.3 Network Access Protocol (NAP)	2-4
2.2.4 IP Layer	2-4
2.2.4.1 Overview of IP Technology	2-4
2.2.4.2 Application of IP to SS7 High-Speed Signaling	2-5
2.2.5 Stream Control Transmission Protocol (SCTP)	2-6
2.2.6 MTP2-User Peer-to-Peer Adaptation Layer (M2PA)	2-6
2.2.7 Signaling Network Layer (MTP - Level 3)	2-7
2.3 Application of IPVHSLs in CCS/SS7 Networks - Topology Overview	2-8
2.3.1 Deployment Drivers	2-8
2.3.2 M2PA IPVHSL Implementation at CCS Network Nodes	2-9
2.3.3 Deployment in CCS Networks	2-10
2.3.4 Potential Use of M2PA IPVHSLs in CCS Network Interconnection	2-12
3. Network Element Requirements	3-1
3.1 Physical and IP Layer Requirements	3-2

3.1.1	Physical Layer Requirements	3-3
3.1.2	IP Layer Requirements	3-4
3.1.2.1	General	3-4
3.1.2.2	IP-Layer Security	3-5
3.2	Stream Control Transmission Protocol (SCTP)	3-6
3.2.1	Functional View of SCTP	3-7
3.2.2	SCTP Protocol Requirements.	3-9
3.2.2.1	Association Initialization	3-10
3.2.2.1.1	Handling of Stream Parameters	3-11
3.2.2.1.2	Destination Transport Address Discovery	3-11
3.2.2.2	User Data Transfer	3-12
3.2.2.3	Congestion Control.	3-13
3.2.2.3.1	Support of SCTP Congestion Control Procedures	3-13
3.2.2.3.2	Impacts of the SCTP Slow-Start Procedure	3-14
3.2.2.4	SCTP Fault Management.	3-15
3.2.2.5	Termination of Association	3-16
3.2.2.6	SCTP Protocol Parameters and Values	3-16
3.3	M2PA Requirements	3-16
3.3.1	Overview of M2PA Functions	3-17
3.3.2	Procedures to Support Signaling Link-Layer Functions	3-17
3.3.2.1	Signal Unit Format, Delimitation, Acceptance.	3-17
3.3.2.2	Client-Server Model.	3-18
3.3.2.3	Establishing and Managing SCTP Associations	3-19
3.3.2.4	Link Alignment	3-19
3.3.2.5	Processor Outage	3-22
3.3.2.6	Level 2 Flow Control	3-22
3.3.2.7	Error Monitoring (Loss of Association)	3-22
3.3.2.8	Performance Monitoring.	3-23
3.3.2.8.1	Performance Monitoring Procedures	3-23
3.3.2.8.2	Performance Monitoring Criteria	3-24
3.3.2.9	Transmission Priorities.	3-25
3.3.3	Procedures to Support the MTP3/M2PA Interface	3-25
3.3.3.1	Sending/Receiving Messages	3-25
3.3.3.2	Link Activation and Restoration.	3-26
3.3.3.3	Link Deactivation	3-26
3.3.3.4	Flush Buffers	3-26
3.3.3.5	Signaling Link Congestion	3-26
3.3.3.6	M2PA Support of Link Changeover	3-26
3.3.4	M2PA Protocol Parameters and Timers	3-26
3.4	Message Transfer Part - Level 3	3-27
3.4.1	Signaling Message Handling	3-27
3.4.1.1	Message Routing	3-27
3.4.1.2	Large Message Handling	3-28

3.4.1.3	Signaling Link Selection	3-28
3.4.1.4	Message Sequencing	3-29
3.4.1.5	Message Handling During Overload.	3-29
3.4.2	MTP Network Management Functions	3-30
3.4.2.1	Congestion Control.	3-31
3.4.2.2	Signaling Link Activation, Restoration, Deactivation, and Link Set Activation	3-33
3.4.2.2.1	General Procedures.	3-33
3.4.2.2.2	Use of Emergency Proving.	3-34
3.4.2.3	Signaling Link Changeover.	3-34
3.4.2.4	Signaling Link Test	3-36
3.4.2.5	Use of the MTP3 Link Oscillation Filter at STPs.	3-36
4.	Node Operations Requirements	4-1
4.1	General	4-1
4.1.1	Scope and Organization.	4-1
4.1.2	Related Operations Requirements	4-2
4.1.3	Additional Source Documents	4-3
4.1.4	Operations Assumptions	4-4
4.2	Configuration Management (CM).	4-5
4.2.1	Provisioning Requirements	4-6
4.2.1.1	General.	4-6
4.2.1.1.1	Configured Resources	4-6
4.2.1.1.2	Descriptive Conventions for CM Data	4-7
4.2.1.2	MTP3 and Common Resources	4-8
4.2.1.2.1	General Provisioning Requirements	4-8
4.2.1.2.2	Common Link Set Parameters.	4-9
4.2.1.2.3	Common Link Parameters	4-10
4.2.1.2.4	M2PA-IPVHSL-Specific Link Parameter Treatment.	4-14
4.2.1.2.5	MTP3 Congestion Thresholds	4-15
4.2.1.3	Network Interfaces	4-17
4.2.1.3.1	IP Interface Port Equipment.	4-18
4.2.1.3.2	IP Interface Physical-Layer Resources	4-19
4.2.1.3.3	IP Interface Data-Link/Data-Network-Access- Layer Resources	4-20
4.2.1.3.4	IP Interface IP-Layer Resources.	4-21
4.2.1.4	SCTP Resources	4-24
4.2.1.5	M2PA Resources	4-27
4.2.1.5.1	M2PA Protocol Parameters	4-27
4.2.1.5.2	M2PA Virtual Links	4-34
4.2.1.6	Link Marginal Performance Thresholds	4-37
4.2.1.7	Summary of Configurable Parameters	4-39
4.2.1.8	Provisioning Operations	4-49
4.2.2	Status Management Requirements.	4-51

4.2.2.1	MTP3 Status Variables	4-52
4.2.2.1.1	Link Set Status	4-52
4.2.2.1.2	Link Status.	4-53
4.2.2.2	M2PA Status Variables	4-55
4.2.2.3	SCTP Status Variables	4-56
4.2.2.4	IP and Physical Layer Resource Status Data.	4-59
4.2.2.4.1	Network Interfaces/Port Equipage	4-59
4.2.2.4.2	Network Interfaces/Local IP Addresses	4-60
4.2.2.5	Status Management Interactions	4-61
4.2.2.5.1	Status Data Retrieval.	4-61
4.2.2.5.2	Status Management Actions	4-62
4.2.2.5.3	Status Change Notifications	4-64
4.2.2.5.4	Status Logging.	4-64
4.3	Fault Management	4-65
4.3.1	Alarm/Event Surveillance.	4-65
4.3.1.1	General.	4-65
4.3.1.1.1	Overview of IPVHSL Alarms.	4-65
4.3.1.1.2	Alarm/Event Notification Contents (Common)	4-67
4.3.1.2	MTP3 Notifications	4-68
4.3.1.2.1	Link Set Outage	4-68
4.3.1.2.2	Link Set Available.	4-69
4.3.1.2.3	Link Unavailable (Link Outage)	4-69
4.3.1.2.4	Link Available	4-70
4.3.1.2.5	Link Failure (MTP3)	4-72
4.3.1.2.6	MTP3 Link Restoration/Activation Failure	4-75
4.3.1.2.7	Sustained Link Failure (Failed Link Craft Referral)	4-77
4.3.1.2.8	Link Inhibit	4-79
4.3.1.2.9	Link Inhibit Denied	4-80
4.3.1.2.10	Link Uninhibit	4-80
4.3.1.2.11	SS7 Link Deactivated/Removed from Service	4-81
4.3.1.2.12	Link Activation Initiated	4-82
4.3.1.2.13	SS7 Link Transmit Congestion Onset/Increase	4-83
4.3.1.2.14	Link Transmit Congestion Abatement.	4-83
4.3.1.2.15	Commencement of SS7 Link Transmit Buffer Overflow	4-84
4.3.1.2.16	Termination of SS7 Link Transmit Buffer Overflow	4-85
4.3.1.2.17	Oversized Message Routing Attempt to an MTP2 Signaling Link.	4-85
4.3.1.3	M2PA Notifications.	4-88

4.3.1.3.1	M2PA Link Out-of-Service	4-88
4.3.1.3.2	M2PA Link In-Service.	4-89
4.3.1.3.3	M2PA Link Alignment/Proving Attempt Failure.	4-90
4.3.1.3.4	Link Local Processor Outage	4-92
4.3.1.3.5	End of Link Local Processor Outage	4-93
4.3.1.3.6	Link Blocked - Remote Processor Outage .	4-94
4.3.1.3.7	Link Unblocked - End of Remote Processor Outage.	4-94
4.3.1.4	SCTP Notifications	4-95
4.3.1.4.1	SCTP Association Established.	4-95
4.3.1.4.2	SCTP Association Terminated.	4-96
4.3.1.5	IP-Layer Notification and Logging.	4-98
4.3.1.5.1	Local IP Address Inactive	4-98
4.3.1.5.2	Local IP Address Active	4-99
4.3.1.5.3	ICMP Error Message Logging and Control .	4-99
4.3.1.6	Network Interface Notifications.	4-101
4.3.2	Testing	4-102
4.3.2.1	IP Router Traceroute Capabilities.	4-102
4.3.2.2	Ethernet Tests.	4-103
4.3.2.2.1	Ethernet TDR Tests.	4-103
4.3.2.2.2	Ethernet Loopback Tests	4-104
4.4	Performance Management.	4-104
4.4.1	Scheduled Traffic and Performance Measurements	4-104
4.4.1.1	General.	4-105
4.4.1.1.1	Overview of IPVHSL Measurement Requirements.	4-105
4.4.1.1.2	General Measurement Requirements . . .	4-106
4.4.1.2	Link Set Measurements (Common).	4-108
4.4.1.3	MTP3 and Common Link Measurements	4-109
4.4.1.4	M2PA Measurements	4-115
4.4.1.5	SCTP Measurements	4-117
4.4.1.6	IP/Network Interface Measurements	4-124
4.4.2	Exception-Based Performance Monitoring	4-129
4.4.2.1	Hourly Thresholding and Alerting for Marginal Performance.	4-129
4.4.2.2	IPVHSL Marginal Performance Reports	4-130
4.4.2.3	Control of Marginal Performance Monitoring . . .	4-131
4.4.2.4	Default Marginal Performance Thresholds.	4-132
5.	Operations Interface Support	5-1
5.1	General	5-1
5.2	Configuration Management/Memory Administration (CM/MA) OS Interface Support.	5-3
5.2.1	For STPs (GR-310-CORE).	5-3

5.2.2	For CCS End-Nodes	5-5
5.2.3	For All CCS Nodes (GR-981-CORE)	5-5
5.3	Maintenance OS Interface Support	5-5
5.3.1	For Fault Management Functions	5-6
5.3.1.1	For All CCS Node Types (TA-TSY-000387)	5-6
5.3.1.2	For STPs (GR-310-CORE)	5-6
5.3.1.3	For SCPs (TA-NWT-000365)	5-7
5.3.2	For Performance Management Functions.	5-7
5.3.2.1	For All CCS Node Types (TA-TSY-000387)	5-7
5.3.2.2	For STPs (GR-310-CORE)	5-8
5.4	Network Data Collection (NDC) OS Interface Support.	5-9
5.4.1	For All CCS Node Types (GR-376-CORE)	5-9
5.4.2	For STPs (GR-310-CORE).	5-9
5.4.3	For SCPs (TA-NWT-000365)	5-11
5.4.4	Nodes Utilizing the GR-310-CORE and TA-NWT-000365 NDC Scheme	5-12
5.4.5	For CCS SOs/SSPs (TR-740)	5-13
5.5	Network Traffic Management (NTM) OS Interface Support	5-13
5.5.1	For All CCS Node Types (GR-495-CORE)	5-13
5.5.2	For STPs (GR-310-CORE).	5-14
5.5.3	NTM Considerations For CCS SOs/SSPs	5-14
5.6	User-System Interface (USI) Support	5-15
6.	Performance.	6-1
6.1	Reliability	6-1
6.2	Network Performance Parameters and Objectives	6-1
6.2.1	Parameters Related to the Message Transfer Part	6-2
6.2.2	Message Transfer Times	6-2
6.2.3	M2PA/SCTP Performance.	6-4
6.2.4	IP Layer Performance	6-4
6.3	Capacity	6-4
7.	Environmental Requirements	7-1
7.1	Power	7-1
7.2	Equipment.	7-1
7.3	Electromagnetic and Electrical Environment	7-1
8.	Quality	8-1
8.1	Introduction.	8-1
8.2	Reliability and Quality Switching Systems Generic Requirements	8-1
8.2.1	System Design and Architecture	8-2
8.2.2	Manufacturing and Production.	8-2
8.2.3	In-Service Performance and Product Support	8-2
9.	Transitional Considerations	9-1
10.	Supplier Support	10-1

10.1	General	10-1
10.2	CCS Node Operations Documentation	10-2
10.3	CCS Node Software Documentation	10-2
	References	References-1
	Acronyms	Acronyms-1
	Requirement-Object Index	ROI-1

List of Figures

Figure 2-1.	Network Architecture for IPVHSLs	2-1
Figure 2-2.	IPVHSL Protocol Architecture	2-3
Figure 2-3.	Potential M2PA IPVHSL Deployment in SCP Access Segment .	2-10
Figure 2-4.	Potential IPVHSLs Deployment in Network Backbone Segment	2-11
Figure 2-5.	Potential Deployment of M2PA IPVHSLs for Network Interconnection	2-13
Figure 3-1.	Resource Model for IPVHSLs	3-2

List of Tables

Table 4-1.	Summary of M2PA IPVHSL Provisioning: Configured Parameters	4-43
Table 4-2.	Suggested Preliminary Default Settings for IPVHSL Marginal Performance Thresholds	4-132